

Hartford Hospital Parking Garage



Location

Hartford CT

Architect

Perkins and Will NY / Desman Associates

Project Type

Medical, Health and Safety Buildings

Parking Structures

Size/Scope of Project

126 panels, 27,500 ft²

(104 Lago panels, 22 Tigris panels)

Customer

Hartford Hospital

Date

2013

Key Contractor

Engineered Building Products Inc.

North American Headquarters

North America

GKDMETALFABRICS

825 Chesapeake Drive

Cambridge MD 21613

Direct: 410.901.8428 or

410.901.8429

metalfabrics@gkdusa.com



This 9-level parking structure provides parking for 1,200 Hartford Hospital employees. Articulated precast panels, woven metal fabric screening and terra cotta colored perforated metal form the exterior facade. The structure connects to an adjacent hospital building by an overhead pedestrian bridge / walkway.

Applications

Parking Facades

Transparent Metal Mesh Facades

Metal Fabrics

Lago

Tigris

System Components

WIB - eyebolts top and bottom

